



Notice-2 to Suppliers/Agents/Manufacturers

Reference to OES-2 requirements page No.(16) Tests on cables, all approved cable manufacturers are requested to submit the **Accelerated Treeing Test** or full type test as per IEC 60502-2 for 11KV & 33KV cables & IEC 60502-1 for LV cables including the **Accelerated aging test**.

Type tests more than five years old & those which not contain full type test as per IEC standards will not be accepted on the re-submission of technical cables details updating.

Therefore, companies not comply with above conditions are requested now to arrange for conducting the test on a reputed third party laboratory (European Only) & to invite DCRP officials to witness the type test.

Deadline for conducting the above mentioned tests is **30th September 2010**. Afterwards any company not conducted the required full type test will be considered not meeting DCRP approval requirements & will be exposed to suspension at any time without any prior notification.

Regards



**Chairman
Distribution Code Review Panel**

Date: 14/10/2009